

PROPOSAL
to
TOWNSHIP OF EGG HARBOR
ATLANTIC COUNTY, NEW JERSEY

MUNICIPAL AID - FY 2020 -
RECONSTRUCTION OF
BLACKMAN ROAD - PHASE 3
CONTRACT NO. 101

SCHEDULE OF QUANTITIES AND PRICES
BASE BID

Pursuant to and in compliance with your Advertisement for Bids and the Information for Bidders relating thereto, the undersigned hereby offers to furnish all plant, labor, materials, supplies, equipment and other facilities and things necessary for, or proper for, or incidental to the **TOWNSHIP CONTRACT 101 - MUNICIPAL AID - FY 2020 - RECONSTRUCTION OF BLACKMAN ROAD -PHASE 3** as required by, and in strict accordance with the applicable provisions of plans and specifications and all addenda issued by the **TOWNSHIP OF EGG HARBOR** or its Engineer prior to the date of opening the bids whether received by the undersigned or not for the amount bid based on the following unit and/or lump sum prices.

NOTE: Extension of Unit Prices must be exact. If there is a discrepancy between the Unit Price and the Amount, the Unit Price will prevail.

Contract Time: **90** Calendar Days
Schedule of Liquidated Damages: **\$500** per calendar day

BASE BID					Unit Price	Write Out Unit Price	Amount
Item	Quantity	Units	Description				
1	1	LUMP SUM	CLEARING SITE	\$		\$	
2	90	C.Y.	ROADWAY EXCAVATION	\$		\$	
3	60	C.Y.	DENSE GRADED AGGREGATE BASE COURSE, 6" THICK	\$		\$	
4	4,850	S.Y.	HMA PROFILE MILLING, 4" & VARIABLE	\$		\$	
5	600	TON	HOT MIX ASPHALT BASE COURSE, MIX 19M64, 2" THICK	\$		\$	
6	600	TON	HOT MIX ASPHALT SURFACE COURSE, MIX 9.5M64, 2" THICK	\$		\$	
7	20	TON	REMOVE & REPLACE ASPHALT DRIVEWAY APRON, 2" THICK	\$		\$	
8	1,020	L.F.	REMOVE & REPLACE CONCRETE VERTICAL CURB	\$		\$	
9	115	S.Y.	REMOVE & REPLACE CONCRETE DRIVEWAY APRON, 6" THICK, IF AND WHERE DIRECTED	\$		\$	
10	1,020	L.F.	REMOVE & REPLACE CONCRETE GUTTER, 8" THICK X 18" WIDE	\$		\$	
11	3	UNIT	CONCRETE HANDICAP RAMP, ADA ACCESSIBLE, W/ DETECTABLE WARNING SURFACE	\$		\$	
12	200	S.Y.	REMOVE & REPLACE CONCRETE SIDEWALK, 4" THICK, IF AND WHERE DIRECTED	\$		\$	
13	97	S.F.	TRAFFIC MARKINGS, LINES, LONG-LIFE, THERMOPLASTIC, 24" THICK	\$		\$	
14	6,300	L.F.	TRAFFIC STRIPES, LINES, LONG-LIFE, EPOXY RESIN, 4" THICK	\$		\$	
15	1,450	L.F.	RUMBLE STRIPS	\$		\$	
16	6	UNIT	REPLACE GRATES W/ BICYCLE SAFE GRATE	\$		\$	
17	2	UNIT	REPLACE CURB PIECE W/ ECO TYPE "N"	\$		\$	
18	2	UNIT	INLETS, TYPE "B" MODIFIED	\$		\$	
19	1	UNIT	INLETS, TYPE "B"	\$		\$	
20	125	L.F.	24" PERFORATED, H.D.P.E. PIPE W/ STONE TRENCH	\$		\$	
21	28	L.F.	15" REINFORCED CONCRETE CULVERT PIPE	\$		\$	

ALL "P" PAGES MUST BE COMPLETED AND SIGNED OR BID SHALL BE REJECTED.

SIGNATURE _____

PROPOSAL
to
TOWNSHIP OF EGG HARBOR
ATLANTIC COUNTY, NEW JERSEY

MUNICIPAL AID - FY 2020 -
RECONSTRUCTION OF
BLACKMAN ROAD - PHASE 3
CONTRACT NO. 101

SCHEDULE OF QUANTITIES AND PRICES
BASE BID

BASE BID

Item	Quantity	Units	Description	Unit Price	Write Out Unit Price	Amount
22	10	UNIT	RESET VALVE BOX	\$		\$
23	8	UNIT	RESET EXISTING CASTING	\$		\$
24	400	S.Y.	TOPSOILING, 4" THICK	\$		\$
25	400	S.Y.	HYDROSEEDING	\$		\$
26	140	HOUR	TRAFFIC DIRECTOR, FLAGGER	\$		\$
27	80	HOUR	TRAFFIC DIRECTOR, FLAGGER 1	\$		\$
28	400	S.F.	CONSTRUCTION SIGNS	\$		\$
29	10	UNIT	DRUM	\$		\$
30	50	UNIT	TRAFFIC CONES	\$		\$
31	4	UNIT	BREAKAWAY BARRICADE	\$		\$
32	1	LUMP SUM	ASPHALT PRICE ADJUSTMENT		THREE HUNDRED DOLLARS AND ZERO CENTS	\$ 300.00
33	1	LUMP SUM	FUEL PRICE ADJUSTMENT		TWO HUNDRED DOLLARS AND ZERO CENTS	\$ 200.00

Total Amount Bid Based on Estimated Quantities, Base Bid Items 1 - 33,
Inclusive

\$ _____

DOLLARS

TOTAL AMOUNT BID FOR BASE BID ITEMS 1-33, WRITTEN

SIGNATURE NAME & TITLE (TYPE OR PRINT)

BID DATE COMPANY NAME

ALL "P" PAGES MUST BE COMPLETED AND SIGNED OR BID SHALL BE REJECTED.

SIGNATURE _____