

PROPOSAL
to
TOWNSHIP OF EGG HARBOR
ATLANTIC COUNTY, NEW JERSEY

2020 ROAD PROGRAM
CONTRACT NO. 102

SCHEDULE OF QUANTITIES AND PRICES

Pursuant to and in compliance with your Advertisement for Bids and the Information for Bidders relating thereto, the undersigned hereby offers to furnish all plant, labor, materials, supplies, equipment and other facilities and things necessary for, or proper for, or incidental to the **TOWNSHIP CONTRACT 102 - 2020 Road Program** as required by, and in strict accordance with the applicable provisions of plans and specifications and all addenda issued by the **TOWNSHIP OF EGG HARBOR** or its Engineer prior to the date of opening the bids whether received by the undersigned or not for the amount bid based on the following unit and/or lump sum prices.

NOTE: Extension of Unit Prices must be exact. If there is a discrepancy between the Unit Price and the Amount, the Unit Price will prevail.

Contract Time: **60** Calendar Days

Schedule of Liquidated Damages: \$500 per calendar day

BASE BID

Item	Quantity	Units	Description	Unit Price	Write Out Unit Price	Amount
1	1	LUMP SUM	CLEARING SITE	\$		\$
2	390	C.Y.	EXCAVATION, UNCLASSIFIED	\$		\$
3	300	C.Y.	DENSE GRADED AGGREGATE BASE COURSE, 6" THICK, TRUCK MEASURE	\$		\$
4	15,770	S.Y.	HMA MILLING, 4" AND VARIABLE	\$		\$
5	2,020	TON	HOT MIX ASPHALT BASE COURSE, MIX 19M64, 2" THICK	\$		\$
6	2,020	TON	HOT MIX ASPHALT SURFACE COURSE, MIX 9.5M64, 2" THICK	\$		\$
7	145	TON	REMOVE & REPLACE ASPHALT DRIVEWAY APRON, 2" THICK	\$		\$
8	1,430	L.F.	6"x18" CONCRETE VERTICAL CURB	\$		\$
9	360	S.Y.	REMOVE & REPLACE CONCRETE SIDEWALK, 4" THICK	\$		\$
10	330	S.Y.	REMOVE & REPLACE CONCRETE DRIVEWAY APRON, 6" THICK	\$		\$
11	6	UNIT	CONCRETE HANDICAP RAMP, ADA ACCESSIBLE, W/ DETECTABLE WARNING SURFACE	\$		\$
12	20,730	L.F.	TRAFFIC STRIPES, LONG-LIFE, EPOXY RESIN - 4" WIDE	\$		\$
13	140	S.F.	TRAFFIC MARKINGS, LINES, LONG-LIFE, THERMOPLASTIC - WIDTH VARIES	\$		\$
14	N/A	N/A	NO LINE ITEM	\$		\$
15	5,185	L.F.	RUMBLE STRIPS	\$		\$
16	11	UNIT	RESET VALVE BOX	\$		\$
17	9	UNIT	RESET EXISTING CASTING	\$		\$
18	2	UNIT	REMOVE EXISTING INLET CASTING	\$		\$
19	2	UNIT	INLET CASTINGS, TYPE "B"	\$		\$

ALL "P" PAGES MUST BE COMPLETED AND SIGNED OR BID SHALL BE REJECTED.

SIGNATURE _____

PROPOSAL
to
TOWNSHIP OF EGG HARBOR
ATLANTIC COUNTY, NEW JERSEY

2020 ROAD PROGRAM
CONTRACT NO. 102

SCHEDULE OF QUANTITIES AND PRICES

BASE BID Item	Quantity	Units	Description	Unit Price	Write Out Unit Price	Amount
20	4	UNIT	REPLACE CURB PIECE W/ ECO TYPE "N"	\$		\$
21	7	UNIT	REMOVE & REPLACE INLET GRATE WITH BICYCLE SAFE GRATE	\$		\$
22	20	L.F.	15" REINFORCED CONCRETE CULVERT PIPE	\$		\$
23	1,520	S.Y.	TOPSOILING, 4" THICK	\$		\$
24	1,520	S.Y.	HYDROSEEDING	\$		\$
25	80	HOUR	TRAFFIC DIRECTOR, FLAGGER	\$		\$
26	80	HOUR	TRAFFIC DIRECTOR, FLAGGER 1	\$		\$
27	400	S.F.	CONSTRUCTION SIGNS	\$		\$
28	10	UNIT	DRUM	\$		\$
29	50	UNIT	TRAFFIC CONES	\$		\$
30	4	UNIT	BREAKAWAY BARRICADE	\$		\$
31	1	LUMP SUM	ASPHALT PRICE ADJUSTMENT	\$	Eight Hundred dollars and zero cents	\$ 800.00
32	1	LUMP SUM	FUEL PRICE ADJUSTMENT	\$	Four hundred dollars and zero cents	\$ 400.00
Total Amount Bid Based on Estimated Quantities, Base Bid Items 1 - 32, Inclusive				\$		\$

DOLLARS
TOTAL AMOUNT BID FOR BASE BID ITEMS 1-32 WRITTEN

SIGNATURE _____ NAME & TITLE (TYPE OR PRINT) _____

BID DATE _____ COMPANY NAME _____

ALL "P" PAGES MUST BE COMPLETED AND SIGNED OR BID SHALL BE REJECTED.

SIGNATURE _____